A Juniper Company

Landscape Maintenance Agreement

Property Name: Patio At Windward

Billing Company Name: Grande Property Services

Description of Services	Frequency
General Maintenance Services	
General Mowing Services- Peak	30
General Mowing Services- OFF Peak	10
General Detailing Services- Peak	7
General Detailing Services- OFF Peak	5
Fertilization Program Turf	4
Fertilization Program Shrub	2
Insect and Disease Control- IPM	12
Irrigation Wet Checks	12
Service Terms	
Annual Maintenance Price	**$116,831.00**

Optional Services

Description of Services	Frequency	Cost per Occ.	Annual Cost

Services

Mowing:

Mowing shall be performed with commercial grade mower types and blades to provide a quality cut. Mower blades will be sharpened between each mowing to prevent tearing of grass blades. Mowing patterns shall be rotated to minimize scalping and rutting by mower wheels and to minimize soil compaction. Bahia & Saint Augustine Turf shall be mowed at a height of 3- 4". Zoysia Turf will be mowed at 1.5-2”. All turf shall be mowed weekly during the growing season of May through October and bi-weekly during the slow growing season of November through April. Should the association request additional cuts, a separate proposal can be provided at the time service is requested. Clippings shall be left on the lawn as long as no visible clumps remain on the grass surface 24 hours after mowing; otherwise, Contractor will collect and dispose of clippings.

Edging:
All hard surfaces shall be edged at every mowing. All soft surfaces (landscape beds), shall be edged every other visit to maintain a clean edge.

Debris Removal:

Contractor shall be responsible for the removal of all lawn debris and visible clippings with each site visit and blowing off all walks, driveways, and street area where debris may be visible.

Bed Weed Control:
All landscape bed areas where weeds are evident will be treated with herbicide to keep these areas relatively weed free. Large weeds will be pulled by hand so as not to be allowed to have enough established quality to detract from the overall aesthetics of the landscape.

Safety Border:

Unless otherwise agreed upon, a 6 inch safety border will be sprayed around all areas where grass grows up to a structure or building, light poles, back flow preventer, screens and other equipment or structures. This safety border is intended to prevent damage to equipment and structure. If the community does not want the safety border, Juniper Landscaping will not be held responsible for damages to these areas.

Pruning:
Shall be performed to maintain the natural shape and plant palette characteristics. Pruning shall include, but not limited to, the removal of vegetation that is dead, damaged, or diseased. When diseased vegetation is removed, the pruning cuts shall be made deep into the healthy plant tissue to re-establish healthy growth. Should flat tops and sides be desired, this will be achieved by the use of gas-powered shears. Should the association request additional trims, an additional services proposal can be provided at the time service is requested. All trimming and pruning shall be subject to all applicable State, Federal, and ANSI (American National Standards Institute) regulations.

Arbor (Below 12 FT):
Trees: Pruned to remove any dead or damaged branches. This will include cross- branching and the raising of canopies to allow safe pedestrian movement on sidewalks and driveways in accordance to good canopy

structure. Trees over 12 feet in overall height requiring service at canopies shall be performed at the Owner's request and expense.
Palms: Fronds shall be removed when frond tips are brown and or damaged with the clean edge cuts made as close to the trunk as possible. Careful trimming procedures shall be followed to prevent damage to any portion of the tree, especially in the crown shaft and bud area. Inflorescence or seedpods and fruit shall be removed on a set cycle. Palms over 12 feet in overall height requiring service at canopies shall be performed at Owner's request and expense.

Fertilization:

Fertilizer services will be overseen by a manager with a Certified Pest Control Operator license. Fertilization will be performed by a technician who is BMP certified and holds a Limited Commercial Fertilizer License issued by the Florida Department of Agriculture and Consumer Services. All fertilizers utilized under this program will be a balanced nutrient package. Only professional commercial grade fertilizers will be used with no less than 50% slow-release nitrogen. Contractor will follow Green Industry Best Management Practices and all state and local fertilizer ordinances. Lawn & ornamentals shall be fertilized as warranted with a commercial fertilizer. The number of applications will be dependent on plant species, site conditions, and fertilizer blends used. Regardless of blends used, Contractor will apply, at a minimum, 4 pounds of nitrogen per 1000 square feet for turf. Ornamentals will vary by species and size. The application of Nitrogen (N) & Phosphorus (P) is prohibited in Florida from June 1st until September 30th. Changes in regulation, outside of Contractor's control, may affect service.

Fertilization

1st Qtr. Application - Turf & Ornamental

2nd Qtr. Application - Turf & Ornamental

3rd Qtr. Application - Turf

4th Qtr. Application - Turf & Ornamental

Pest, Weeds & Disease:

Spray services will be overseen by a manager with a Certified Pest Control Operator license. Spraying will be performed by a technician who holds a Spray ID card issued by the Florida Department of Agriculture and Consumer Services. The control of weeds will be a utilization of liquid and granular applications to areas of

infestation. Inspection of the turf and plant material shall be done regularly, with applications performed on a 4-6 week cycle as needed to treat various, controllable pests. Areas will be treated as problems occur. Changes in regulation, outside of Contractor's control, may affect service.

Weed: Weed control will be rotated on an 4-6 week cycle and can only be applied safely when wind drift is at a minimum, and in some cases, when average ambient temperature does not exceed manufacturer's label recommended maximum. The control of Crab, Common Bermuda, Torpedo, Tropical Signal and other true grasses in turf excluded from this Contract. In some cases, regulation prevents ability to control and in others there is no permanent eradication and control product. Preemergent applications are not included in this contract unless otherwise agreed upon by Owner & Contractor.

Pest: Preventative Grub, Chinch Bug & Fire Ant control is excluded from this Contract unless otherwise agreed upon by Owner & Contractor. A preventive application reduces but does not eliminate the potential of an outbreak. Areas will be spot treated, when identified, as part of an inspection. A proposal will be provided by Contractor, on request from Owner, for preventative treatment options. Nematode, Tuttle Mealybug & Stunt Mite, Azalea Lace Bug, Royal Palm Bug & White Fly control are entirely excluded from this Contract though some may have treatment options. Those treatments will be proposed at request from Owner.

Disease: Preventative fungal turf diseases are excluded from this contract unless otherwise agreed upon by Owner & Contractor. Preventive applications for certain diseases can be made to reduce the potential of an outbreak and will be proposed on request from Owner. A preventive application reduces, but does not eliminate, the potential of an outbreak. Lethal Virus Necrosis, Take All Root Rot, Large Patch. Sphaeropsis Gall, Fusarium Wilt, Ganoderma Butt Rot, Lethal Bronzing & Bothryosphaeria Canker are entirely excluded from this Contract. Curable disease treatments will be proposed at request from Owner.

Irrigation:

Wet Checks: Contractor shall perform a routine monthly maintenance inspection of the irrigation system consisting of the following: Activate and inspect each zone of the existing system, visually inspect surface for leaks, adjust and clean sprinkler heads where needed & inspect control valves and valve boxes.

Technician Adjustments: Adjust controller to the watering needs and in accordance with state and local ordinances as dictated by site conditions.

All parts needed to maintain functionality of the system will be proposed when exceeding $500.00. All repairs made, under $500.00 will be scheduled as discovered. Owner authorizes all repairs under this threshold as part of this Contract. This is a per service threshold, not cumulative. For all repairs in excess of $500.00, work will not commence until signed off by an authorized representative of the Owner. Irrigation service calls required between scheduled visits will be billed on a time and material basis unless otherwise agreed upon by Owner & Contractor. Emergency service calls, defined as repairs that are not within normal operating hours (Monday through Friday 8:00am-4:00pm) and on holidays, will be billed on a time and material basis but at time and a half rate. There is a minimum $200.00 service fee which includes the first 2 hours of service.

By state law, any rain sensors found to be in non-working order will be replaced at Owner's expense. Contractor shall not be responsible for the maintenance or performance of the water source. Contractor is not responsible for the availability of water or the quality of water which results in insufficient volume,

pressure, or excessive clogging of nozzles and filters. In instances where poor water quality diminishes the performance of the system, Contractor will propose remedy. Contractor will not be liable for damages as a result insufficient water volume, pressure or quality. In extreme cases, it may be necessary to increase the number of contractual wet checks to keep up with the obstructions in the system. Contractor shall perform a full irrigation audit for the purpose of budgeting long term repairs and renovations at Owner's request and expense.

Non-Contractual Services:

Unless otherwise agreed upon, in writing, by Owner & Contractor, these services include, but are not limited to, tree, palm, plant or turf replacements, irrigation or landscape lighting repairs, mainline, pump station, or water source repairs, drainage work, arbor work, preventative disease & pest treatment, pre-emergent weed control, annual flower rotations, mulch applications, additional services above and beyond contracted frequency, storm preparation or reparation or any requested changes or enhancements to property.

Contractor will make recommendations as needed as well as act on recommendations from Owner. These services will be proposed and billed on a time and material basis. All non-contractual services will not commence without signed, written permission from authorized representative of Owner. In some cases, proposals can be definitive and in others where discovery is involved, Contractor will provide best estimate of cost but will vary based on the work involved. In these cases, detail will be provided to support the cost. Due to the volatility in labor and material cost, and Contractor's inability to budget for non-contractual services, pricing will always be based on cost at time of service.

Discovery Period:

As part of the discovery period, Contractor will provide to Owner, a start-up plan detailing first 90 days of service. This will include the existing deficiencies report, described below, as well as expectations for milestones achieved in each of the thirty (30), sixty (60) & ninety (90) day periods. Start up plan may vary on smaller properties.

Contractor will utilize the first ninety (90) days of service to identify existing deficiencies on site. Issues include, but are not limited to, negligent pruning or mowing, excessive debris, high or low pH in soil, insufficient cation exchange rate, poorly drained areas, all malfunctioning or non-operational irrigation or landscape lighting, water quality, volume or pressure issues and active disease or pests affecting trees, palms, ornamentals or turf. Depending on the level of deficiency and property size this may be completed sooner but it may also exceed the ninety (90) day benchmark. In the event evaluation will exceed ninety (90) days, Contractor will notify Owner and set a new expectation.

Once evaluation is complete, Contractor will provide a detailed issues report along with proposals for remediation. Owner has an obligation to either approve remediation work or waive Contractor's liability for pre-existing deficiencies, including future damages they may cause.

Terms & Conditions:

This Contract shall be for an initial term of twelve (12) months, beginning on the contractual start date listed in this Agreement. The Contract shall not automatically renew. Any continuation beyond the initial twelve (12) month term must be agreed upon in writing by both parties.

For the 2026 contract year, pricing shall remain at the agreed amount with no increase. Thereafter, any proposed annual increase shall not exceed three percent (3%) unless otherwise justified in writing by the Contractor and approved by the Association's Board of Directors.

Either party may terminate this Agreement at the end of the twelve (12) month term by providing thirty (30) days' written notice without cause. During the term, either party may terminate this Agreement for cause by providing written notice of deficiencies in the performance of contracted services. The party receiving such notice shall have fifteen (15) days to remedy the deficiencies. If deficiencies are not corrected, termination

shall become effective thirty (30) days after receipt of the termination notice.

In the event of termination, the Owner shall remain responsible for payment of all services properly rendered up to the effective termination date, in lieu of the level billing structure established for convenience to the Owner.

Standard Warranty:

Contractor agrees to warranty Juniper installed irrigation, drainage and lighting for one (1) year, trees and palms for six (6) months, shrubs and ground cover for three (3) months, and sod for thirty (30) days. All products used by Contractor in the service of executing Contract scope are purchased from professional green industry vendors and manufacturers. Contractor is not responsible for damages due to acts of God or damages by others. This includes, but is not limited to freeze damage, tornadoes, hurricanes, strong winds, lightning, excessive water, insufficient water, poor existing soil conditions, poor drainage, disease, pest. Any losses due to Acts of God or damages by Others, whether primary or secondary are the sole liability of the Owner. Warranty is not valid for any relocated materials, materials provided by others or and materials that do not have an automatic irrigation system supplying supplemental water. Warranty is not valid for failure of water or power supply. Juniper is not responsible for damage to non-located underground. Juniper maintaining a property, alone, does not constitute warranty of issues on that property.

Fees and Costs:

In the event of a payment default, Owner shall be responsible for paying the costs Contractor incurs to collect any unpaid balance, including but not limited to, attorney's fees and court costs. Past due, unpaid balance shall accrue interest at the highest lawful rate specified in the Florida statutes until paid in full.

PAYMENT SCHEDULE

SCHEDULE	PRICE	SALES TAX	TOTAL PRICE
January	$9,735.92	$0.00	$9,735.92
February	$9,735.92	$0.00	$9,735.92
March	$9,735.92	$0.00	$9,735.92
April	$9,735.92	$0.00	$9,735.92
May	$9,735.92	$0.00	$9,735.92
June	$9,735.91	$0.00	$9,735.91
July	$9,735.92	$0.00	$9,735.92
August	$9,735.91	$0.00	$9,735.91
September	$9,735.92	$0.00	$9,735.92
October	$9,735.91	$0.00	$9,735.91
November	$9,735.92	$0.00	$9,735.92
December	$9,735.91	$0.00	$9,735.91
	$116,831.00	**$0.00**	**$116,831.00**

By Edward Tanguay

Print Name Edward Tanguay Jr.

Date 12/22/2025

Juniper Landscaping of Florida LLC

By Diana Stanislav

Print Name Diana Stanislav

Date 12/22/25

Patio At Windward